

Date: Wednesday, 2/15/2006 3:46:06 PM
 User: Kim Johnston

Process Sheet

Customer : CU-DAR001 Dart Helicopters Services	Drawing Name : SADDLE FITTING, FWD (OUTBOARD/INBOARD)
Job Number : 25830	
Estimate Number : 10531	
P.O. Number : N/A	Part Number : D2572
This Issue : 2/15/2006 S.O. No. : N/A	Drawing Number : D2572 REV DE 06.02.16
Prsht Rev. : NC	Project Number : N/A
First Issue : N/A Type : MACHINED PARTS	Drawing Revision : DE
Previous Run : 2433	Material : WA
Written By : SEE COMMENT BELOW	Due Date : 3/15/2006 Qty: 15 Um: Each
Checked & Approved By : JG 06.02.16	
Comment : Est: 1 02.19.02 Re-format; Change to Dwg Rev. D & incorporated D2572KJ	

Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
----------------	------------------------------	----------------------

1.0	D6101005	7075-T7351 8.25X5.0X2.5
-----	----------	-------------------------



Comment: Qty.: 15.0000 Each(s)/Unit Total : 15.0000 Each(s)
 7075-T7351 8.25X5.0X2.5
 Make from D6101-005 billet for D2572
 Ensure that grain is along 5.00" length
 Batch No: 823940

BG
FOR
EO

J.G. 06/02/21

10

2.0	HAAS1	HAAS CNC VERTICAL MACHINING #1
-----	-------	--------------------------------



Comment: HAAS CNC VERTICAL MACHINING #1
 Program Batch No. 25830 Double check by: BG

1-Machine Step No 1 per Folio FA051 and inspect per attached Dimension Sheets
 2-Machine Step No 2 per Folio FA051 and inspect per attached Dimension Sheets
 3-Machine Step No 3 per Folio FA051 and inspect per attached Dimension Sheets
 4-Deburr and remove all machining marks
 5-Tumble to remove sharp edges.

BG
FOR
EO

J.G.

06/02/21

10

3.0	MILLING CONV.	CONVENTIONAL MILLING MACHINE
-----	---------------	------------------------------



Comment: CONVENTIONAL MILLING MACHINE
 Machine keyway as per dwg D2571 & D2572

BG
FOR
EO

J.G.

06/02/25

10

Dart Aerospace Ltd

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Wednesday, 2/15/2006 3:46:07 PM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: SADDLE FITTING, FWD (OUTBOARD/INBOARD)

Job Number: 25830

Part Number: D2572

Job Number:



Seq. #:

Machine Or Operation:

Description :

4.0

QC2

INSPECT PARTS AS THEY COME OFF MACHINE



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

BE for EQ / J.G.

06/02/05

10

5.0

QC8

SECOND CHECK



Comment: SECOND CHECK

BC

06-02-27

10

6.0

HAND FINISHING1

HAND FINISHING RESOURCE #1



Comment: HAND FINISHING RESOURCE #1

Acid etch and Alodine as per QSI 005 4.1

SAD

06:03:05

(10)

7.0

POWDER COATING

POWDER COATING



Comment: POWDER COATING

Powder Coat White Gloss (Ref: 4.3.5.1) as per QSI 005 4.3

a.m. 06-03-06

8.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



Comment: INSPECT POWDER COAT

M

06 03 07

(10)

9.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: *ST479*

C 206/03/08

(10)

10.0

DC

DOCUMENT CONTROL



Comment: DOCUMENT CONTROL

Inspection Level 21

(10)

06/03/08

Job Completion



U 06-03-08

Dart Aerospace Ltd

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

DART AEROSPACE LTD	Work Order:	25830
Description: Saddle, Fwd Inboard	Part Number:	D2572
Inspection Dwg: D2572 Rev. E		Page 1 of 1

Inspect dimensions highlighted on inspection sheet drawing D2572 Rev. E and record below:

				Recorded Actual Dimensions					
Dim	Min	Max	Go/No Go Gauge	1	2	3	4	By	Date
A	0.438	0.443	DT8682	0.438	0.438	0.438	0.438		
B	1.745	1.755		1.745	1.746	1.747	1.746		
C	3.495	3.505		3.496	3.496	3.497	3.497		
D	1.745	1.755		1.745	1.746	1.747	1.746		
E	7.990	8.010		8.003	8.003	8.003	8.004		
F	0.490	0.510		0.492	0.499	0.498	0.494		
G	0.257	0.262	DT8683	0.257	0.257	0.257	0.257		
H	0.375	0.380	DT8684	0.375	0.375	0.375	0.375		
I	0.490	0.510		0.496	0.494	0.493	0.498		
J	1.174	1.184		1.177	1.178	1.178	1.177		
K	0.558	0.578		0.563	0.564	0.566	0.565		
L	1.174	1.184		1.177	1.178	1.178	1.177		
M	1.490	1.500		1.493	1.492	1.494	1.492		
N	2.495	2.505		2.496	2.497	2.498	2.495		
O	3.869	3.879		3.871	3.871	3.873	3.873		
P	0.115	0.135		0.125	0.125	0.124	0.124		
Q	0.115	0.135		0.130	0.130	0.130	0.130		
R	0.240	0.260		0.252	0.252	0.251	0.253		
S	0.115	0.135		0.126	0.124	0.126	0.127		
T	0.178	0.198		0.188	0.188	0.188	0.188		
U	2.940	2.980		2.960	2.960	2.960	2.960		
V	0.230	0.250		0.233	0.234	0.235	0.235		
W	0.115	0.135		0.124	0.125	0.126	0.124		
X	0.307	0.312		0.310	0.310	0.310	0.310		
Y	0.760	0.765		0.760	0.760	0.760	0.760		
Z	0.352	0.372		0.360	0.360	0.360	0.360		
AA	0.470	0.530		0.500	0.500	0.500	0.500		
AB	0.615	0.635		0.626	0.627	0.629	0.626		
AC	0.053	0.073		0.063	0.063	0.063	0.063		
AD	0.240	0.260		0.247	0.244	0.242	0.247		
AE	1.375	1.395		1.393	1.390	1.388	1.388		
AF	0.115	0.135		0.130	0.130	0.130	0.130		
AG	0.240	0.280		0.250	0.250	0.250	0.250		
AH	0.240	0.260		0.245	0.247	0.245	0.245		
AI	2.000	2.020		N/A	N/A	N/A	N/A		
AJ	0.023	0.043		0.030	0.030	0.030	0.030		
Accept/Reject									

Measured by:	Er
Date:	06/02/24

Audited by:	rmf
Date:	06/02/24

Rev	Date	Change	Revised by	Approved
A		New Issue	RF	
B	02.09.24	Re-format; Added Rev. D	KJ	
C	02.10.11	Re-format; Added DT8682, DT8683, DT8684	KJ	
D	05.05.05	Added dimension AI	KJ/RF	
E	05.12.05	Added dimension AJ	KJ/JLM	

DART AEROSPACE LTD	Work Order:	25830
Description: Saddle, Fwd Inboard	Part Number:	D2572
Inspection Dwg: D2572 Rev. E		Page 1 of 1

Inspect dimensions highlighted on inspection sheet drawing D2572 Rev. E and record below:

				Recorded Actual Dimensions					
Dim	Min	Max	Go/No Go Gauge	1	2	3	4	By	Date
A	0.438	0.443	DT8682	0.438	0.438	0.438	0.438		
B	1.745	1.755		1.747	1.746	1.746	1.747		
C	3.495	3.505		3.496	3.498	3.497	3.497		
D	1.745	1.755		1.747	1.746	1.746	1.747		
E	7.990	8.010		8.004	8.002	8.002	8.003		
F	0.490	0.510		0.496	0.497	0.497	0.498		
G	0.257	0.262	DT8683	0.257	0.257	0.257	0.257		
H	0.375	0.380	DT8684	0.375	0.375	0.375	0.375		
I	0.490	0.510		0.503	0.496	0.500	0.500		
J	1.174	1.184		1.178	1.177	1.177	1.177		
K	0.558	0.578		0.568	0.565	0.568	0.569		
L	1.174	1.184		1.178	1.177	1.177	1.177		
M	1.490	1.500		1.494	1.492	1.492	1.493		
N	2.495	2.505		2.496	2.498	2.498	2.498		
O	3.869	3.879		3.873	3.873	3.873	3.874		
P	0.115	0.135		0.121	0.123	0.123	0.124		
Q	0.115	0.135		0.130	0.130	0.130	0.130		
R	0.240	0.260		0.252	0.251	0.249	0.250		
S	0.115	0.135		0.123	0.125	0.125	0.129		
T	0.178	0.198		0.188	0.188	0.188	0.188		
U	2.940	2.980		2.960	2.960	2.960	2.960		
V	0.230	0.250		0.237	0.233	0.233	0.234		
W	0.115	0.135		0.121	0.124	0.124	0.127		
X	0.307	0.312		0.310	0.310	0.310	0.310		
Y	0.760	0.765		0.760	0.760	0.760	0.760		
Z	0.352	0.372		0.360	0.360	0.360	0.360		
AA	0.470	0.530		0.500	0.500	0.500	0.500		
AB	0.615	0.635		0.623	0.624	0.624	0.624		
AC	0.053	0.073		0.063	0.063	0.063	0.063		
AD	0.240	0.260		0.245	0.247	0.247	0.248		
AE	1.375	1.395		1.389	1.387	1.388	1.388		
AF	0.115	0.135		0.130	0.130	0.130	0.130		
AG	0.240	0.280		0.250	0.250	0.250	0.250		
AH	0.240	0.260		0.248	0.245	0.247	0.247		
AI	2.000	2.020		N/A	N/A	N/A	N/A		
AJ	0.023	0.043		0.030	0.030	0.030	0.030		
Accept/Reject									

Measured by:	EP / J.G.
Date:	06/02/25

Audited by:	J.G.
Date:	06/02/25

Rev	Date	Change	Revised by	Approved
A		New Issue	RF	
B	02.09.24	Re-format; Added Rev. D	KJ	
C	02.10.11	Re-format; Added DT8682, DT8683, DT8684	KJ	
D	05.05.05	Added dimension AI	KJ/RF	
E	05.12.05	Added dimension AJ	KJ/JLM	

DART AEROSPACE LTD	Work Order:	25830
Description: Saddle, Fwd Inboard	Part Number:	D2572
Inspection Dwg: D2572 Rev. E		Page 1 of 1

Inspect dimensions highlighted on inspection sheet drawing D2572 Rev. E and record below:

				Recorded Actual Dimensions					
Dim	Min	Max	Go/No Go Gauge	1	2	3	4	By	Date
A	0.438	0.443	DT8682	0.438	0.438				
B	1.745	1.755		1.747	1.747				
C	3.495	3.505		3.500	3.499				
D	1.745	1.755		1.747	1.747				
E	7.990	8.010		8.002	8.002				
F	0.490	0.510		0.499	0.498				
G	0.257	0.262	DT8683	0.257	0.257				
H	0.375	0.380	DT8684	0.375	0.375				
I	0.490	0.510		0.498	0.499				
J	1.174	1.184		1.177	1.177				
K	0.558	0.578		0.568	0.567				
L	1.174	1.184		1.177	1.176				
M	1.490	1.500		1.494	1.493				
N	2.495	2.505		2.499	2.498				
O	3.869	3.879		3.871	3.872				
P	0.115	0.135		0.125	0.127				
Q	0.115	0.135		0.130	0.130				
R	0.240	0.260		0.241	0.242				
S	0.115	0.135		0.127	0.127				
T	0.178	0.198		0.188	0.188				
U	2.940	2.980		2.960	2.960				
V	0.230	0.250		0.240	0.241				
W	0.115	0.135		0.125	0.137				
X	0.307	0.312		0.310	0.310				
Y	0.760	0.765		0.760	0.768				
Z	0.352	0.372		0.360	0.360				
AA	0.470	0.530		0.500	0.500				
AB	0.615	0.635		0.627	0.628				
AC	0.053	0.073		0.063	0.063				
AD	0.240	0.260		0.244	0.244				
AE	1.375	1.395		1.361	1.361				
AF	0.115	0.135		0.130	0.130				
AG	0.240	0.280		0.250	0.250				
AH	0.240	0.260		0.250	0.249				
AI	2.000	2.020		N/A	N/A				
AJ	0.023	0.043		0.030	0.030				
Accept/Reject									



Measured by:	S.G.
Date:	06/02/25

Audited by:	Ep
Date:	06/02/25


Rev	Date	Change	Revised by	Approved
A		New Issue	RF	
B	02.09.24	Re-format; Added Rev. D	KJ	
C	02.10.11	Re-format; Added DT8682, DT8683, DT8684	KJ	
D	05.05.05	Added dimension AI	KJ/RF	
E	05.12.05	Added dimension AJ	KJ/JLM	

RELEASED

05.12.06



SECTION A-A



0.438±0.005
(TYP 4 PLACES)

0.500

0.060


R0.025
(TYP)

NOTES

MATERIAL: 7075-T7351 (QQ-A-250/12)
(REF DART SPEC. D6102-003)
FINISH: ACID ETCH, ALODINE PER DART QSI 005 4.1
POWDER COAT GLOSS WHITE (REF 4.3.5.1) PER
DART QSI 005 4.3
BREAK ALL SHARP EDGES 0.010 TO 0.020
TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED

- 1 ENGRAVE PART AND BATCH NUMBER IN THIS AREA TO MAX DEPTH OF 0.010
2 CHAMFER 0.063" x 45° AROUND THIS SURFACE (TYPICAL 2 PLACES)
3 CHAMFER 0.063 x 45° ALL AROUND
4 CHAMFER 0.033 x 45° (SEE DETAIL C) E

VIEW B-B



E	05.07.13	ADD CHAMFER ON RIDGE NOTE 4
D	02.09.06	ADD RIDGES; TIGHTEN TOLERANCES
C	99.10.22	INCORP. DEO 9123/9079/9102 ADD DIMENSIONS PER TSR A1177
B	96.12.02	ADD GRAIN DIR., 0.438 WAS 0.425
A	96.09.16	NEW ISSUE

DESIGN	DS	DRAWN BY	PH	DART	DART AEROSPACE LTD.
CHECKED	#	APPROVED	#	DRAWING NO.	REV. E
DATE	05.07.13	TITLE	INNER FWD SADDLE	D2572	SHEET 1 OF 1
		SCALE			2:3

COPYRIGHT © 2006 BY DART AEROSPACE LTD.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL
AND IS SUPPLIED ON THE EXPRESS CONDITION
THAT IT IS NOT TO BE USED FOR ANY PURPOSE
OR COPIED OR COMMUNICATED TO ANY OTHER
PERSON WITHOUT WRITTEN PERMISSION FROM
DART AEROSPACE LTD.

DETAIL C
SCALE 2:1

SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. 25830